BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2015-16/OW/WORK_INDENT18320/CALL-2

APPROVED SCHEDULE - B

EE/BTP/BBMP/E-PMT/03/2015-16, Date: 22.01.2016

Development of tatanagara 4th cross children's park in ward no. 8, kodigehalli

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of K R Taranath		
				In Figures		In Words
1	1160	Clearing and grubbing land including uprooting rank vegetation, grass, brush, shrubs, saplings and trees of girth upto 300mm by manual means in area of light jungle, removal of stumps, disposal of unserviceable materials, stacking of serviceable materials, labour charges compelte as per specifications.	sqm	6.35	7366.00	Rupees Six and Thirty Five Paise Only
2	2023.62	Construction of embankment with approved material gravel/murrum with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement table 300-2 complete as per specifications, including cost of gravel / murum, watering charges and compaction by vibratory roller to 95% of proctor density as directed by the Engineer-in-charge of the work	cum	304.82	616839.85	Rupees Three Hundred Four and Eighty Two Paise Only
3	9.06	Earth work in surface excavation in ordinary soil for leveling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe line and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed as per specifications	cum	156.64	1419.16	Rupees One Hundred Fifty Six and Sixty Four Paise Only
4	9.06	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 2.00 Km	cum	77.39	701.15	Rupees Seventy Seven and Thirty Nine Paise Only
5	12	Supplying and Providing Sand	cum	1666.0	19992.00	Rupees One Thousand Six Hundred Sixty Six Only
6	652	Providing and fixing Pre cast solid concrete kerb stones made out of CC 1:2:4 of size 450x200x400 mm and finished with CM 1:3 plastering and finishing cutting etc., complete	No.	366.21	238768.92	Rupees Three Hundred Sixty Six and Twenty One Paise Only
7	631.2	Providinga and applying ready mix priming coat over ocncrete / masonry, / asbestos cement sheet / plastered surfaces includding preparing the surface after thorougly cleaning of oil, grease, dirt and other foreign matter and sand papering including cost of materials, labour compelte as per specifications	sqm	26.46	16701.55	Rupees Twenty Six and Forty Six Paise Only
8	631.2	Providing and applying spray painting in two coast (excluding priming coat) over ocncrete / masonry, / asbestos cement sheet / plastered surfaces includding preparing the surface after thorougly cleaning of oil, grease, dirt and other foreign matter and sand papering including cost of materials, labour compelte as per specifications	sqm	66.68	42088.42	Rupees Sixty Six and Sixty Eight Paise Only
9	261	KSRB- 15-18.2 : Providing and applying enamel metal paint two coats (excluding priming coat) over new steel or other metal surface brushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materials, labour, complete as per specifications	sqm	83.61	21822.21	Rupees Eighty Three and Sixty One Paise Only

taaranath

Executive Engineer
Byatarayanapura Division
Yelahanka Zone, B.B.M.P.
Bangalore - 560 092
9/3/16

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of K R Taranath		
				In Figures		In Words
10	1	Providing Children Play Two Seater Standard SWing Equipment: This sWing' consist of 2 Nos. seats of solid metal seats powder coated of Size-500mmx 250mm x 16 SWG supported by MS chains of Length 1.8mtrs, each seat is suspended by 1 line of chain. The chains are supported by circular housingswith bearing from which the chain in suspended. The beam is of 50mm MS tAt class pipe. Size of MS • chain 30mm x 20mm x 5mm thick, the length of the main beam is 2.40 mtrs and No. 1 24800.00 25300.00 28400.00 24000.00 -263.00.00 *·Lowestheight 2.00mtrs. The 2 Nos of cost iron-heads. Four footing are in 42mm pipes. All pipes are of ISI grade. All the pipes are painted with two coats of superset paint over a coat of protective Zinc chromate yellow oxide including fiXing the play equipments in CC 1:2:4, curing etc., complete with all lead, lift. loading. unloading and any other incidental charges and as per the drawing and specification and directionof the Engineerin chargeof the work.. 2lp	No.	25872.0	25872.00	Rupees Twenty Five Thousand Eight Hundred Seventy Two Only
11	1	Providing Children Play Merry-Go-Round Equipment: Made of MS. 'A' class pipes. Main pillars are in 100mm, fitted with shaft and two bearings and other cross members are in 25 & 20mm MA 'A' Class pipes, bottom ring is made out of 25mm 0 ring size is 1.20 mtrs Dia, fitted with four seats are in mental sats of 250 x 200 x 18SGE, handles are made out of 20mm NB pipes and other supports are in 25mm MS 'N class pipes. All the pipes are painted with two coats of super set paint over a coat of protective Zinc chromate yellow including fixing the play equipments in CC 1:2:4, curing etc., complete with all lead, lift, loading, unloading and any other incidental charges and as per the drawing and specification and direction of the EnQlneer In enarce of the work	No.	27440.0	27440.00	Rupees Twenty Seven Thousand Four Hundred Forty Only
12	1	pro~Mjng Children Play Two Seater Swing Duck Equipment: This swing consist of 2 Nos. FRP Ducks supported by MS chains of Length 1.05mtrs, each duck Is suspended by 3 lines of chains. The chains are supported by circular housings with bearing from which the chain in suspended. The main beam is of 42mm MS 'A' class pipe. Size of MS chain 30mm x 20mm x 5mm thick, the length of the main beam is 2.40 mtrs and height 1.95mtrs. Four footing are in 42mm pipes. All pipes are of ISI grade. All the pipes are painted with two coats of super set paint over a coat 0 protective Zinc chromate yellow oxide including fixing the play equipments in CC 1:2:4, curing etc., complete with all lead, lift, loading, unloading and any other incidental charges and as per the drawing and specification and direction of the Enalneer in charae of the work.	No.	30184.0	30184.00	Rupees Thirty Thousand One Hundred Eighty Four Only
13	10	Providing Sitting chairs made of RCC including steel reinforcement as per the directions of the Engineer-in-charge of the work	No.	6468.0	64680.00	Rupees Six Thousand Four Hundred Sixty Eight Only
14	0.63	Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220 kgs with 40mm and down size graded granite metal coarse aggregates @ 0.892cum and fine aggregares @ 0.465 cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications	Cum	5132.18	3233.27	Rupees Five Thousand One Hundred Thirty Two and Eighteen Paise Only

tadoranth

Executive Engineer
Byatarayanapura Division
Yelahanka Zone, B.B.M.P.
Bangalore - 560 092
19/3/16

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of K R Taranath		
				In Figures		In Words
15	0.84	Providing and laying in position plain cement concrete of mix M20 with OPC cement @ 300 kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.64 cum and fine aggregares @ 0.43 cum with superplastisiser @ 3lts confirming to IS9103-1999 reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications	cum	5872.0	4932.48	Rupees Five Thousand Eight Hundred Seventy Two Only
16	84.6	Supplying and fixing MS rectangular poles made out of 2 equal angles of 65x65x6 mm welded together and fixed in CC 1:2:4 with 2 No. of 16mm dia MS hold fast rods each of length 25 cm, including ocst of all materials, cutting, bending, scaffolding wherever necessary, nicely finishing the welded joints with all leads and lifts and as per the directions of the Engineer in charge of the work and including providing 2 coats of approved quality paint over one coat of shop painting (excluding cost of earthwork and concrete)	m	971.61	82198.21	Rupees Nine Hundred Seventy One and Sixty One Paise Only
17	348	Providing and fixing MS block pipe of 38 mm dia of heavy guage of 14 including removing the bends, cutting the pipe, and fixing pipe in between the existing two verticle poles (MS rectangular poles) and spot welding the chain link with MS block pipe including cost of all materials, wastage in cutting and scaffolding whereever necesssary with all lead and lift as directed by the Engineer in charge of the work and including providing 2 coats of approved quality paint over one coat of shop paint	m	331.28	115285.44	Rupees Three Hundred Thirty One and Twenty Eight Paise Only
18	174	Providing chainlink fencking 50mm size of 8 guage properly stretched between existing rectangular poles andfixed with suitable bolts and nuts, the free ends shall be welded to the pole and block pipe at top and bottom as required including cost of all materials, labour, lead and lifts as per the direcdtions of the Engineer in charge of the work and including providing 2 coats of approved quality paint over one coat of shop paint	sqm	683.73	118969.02	Rupees Six Hundred Eighty Three and Seventy Three Paise Only
					1438493.68	

Taranath

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

19/3/16

19/03